

**DOCUMENT 00901**  
**ADDENDUM NUMBER 02**

**DATE:** September 16, 2009  
**PROJECT:** Fleet Manager's Office  
**PROJECT NUMBER:** PWT-0902  
**OWNER:** City of Arlington  
**CONSULTANT:** HPM Engineers  
2510 Tarpley Road, Ste. 4  
Carrollton, Texas 75006  
Ph. (214) 483-6202  
**TO:** Prospective Bidders

This Addendum forms a part of the Contract Documents and modifies the Bidding Documents dated September 14, 2009 with amendments and additions noted below. Acknowledge receipt of this Addendum in the space provided in the Bid Form. Failure to do so may disqualify the Bidder.  
This Addendum consists of (1) pages.

Item No. 1 On sheet A2, drawing 1. Add a 48" AFF wainscot of 3/4" CDX plywood on the warehouse side of the east wall for Office 1-03 and Admin 1-02. The wainscot will extend from the north wall of the warehouse to the north edge of the door frame for door 1-01.

Item No. 2 Clarification for contractor question regarding the route of the heat pump unit lines route through the steel cage located on the interior side of the wall: The heat pump unit line set is not required to be encased where it is routed exterior to the building. The line set piping shall be routed interior to the building to the extent possible. The Contractor's bid shall anticipate penetration of the block wall where the line set exits the building.

**END OF ADDENDUM NO. 2**

X:\Construction Management\Support\Projects\Active Projects\PWT-0902 Fleet Manager's Office\401 Const Documents\4010 Addenda\Addendum1-2009-9-16.doc